

LIST OF MATERIALS

- (1) Raintight Cap
- (2) 2" Galvanized Rigid Steel Conduit
- (3) 2 1/2" To 2" Galvanized Steel Reducer
- (4) 2 1/2" Galvanized Rigid Steel Conduit
- (5) 1/2" Set Screw (Typ. 4 Each)
- 6 1" Rigid Steel Conduit, Strap To Mast Install Bushing On Top Of Conduit
- (7) 3" Galvanized Rigid Steel Conduit
- (8) PVC To Rigid Steel Conduit Fitting
- (9) Concrete Foundation, Class "B"
- (10) 1" PVC Conduit To Radio Transceiving Unit
- (11) #5 Rebar (8" Length) Welded To 3" Conduit (Typ. - 4 Each)
- (12) 5/8" ϕ x 8' Long Grounding Rod
- (13) Acorn Nut Connection
- Ground Attached To 3" Conduit
 Using Lug And Self Tapping Screw

2398 City of Scottsdale Standard Details

ANTENNA MAST DETAIL

2398