



- The total amount of sound panels will be roughly 460lf.
- The panels support poles will be installed 9' deep into the ground.
- The panels will be installed 24' tall (3EA 8' tall panels stacked on top of one another).
- We are proposing a 16' wide x 20' tall gate for access/egress. This will help with getting equipment in and out of the site.
- Most the panels are gray in color with a few tan colored panels.
- The panels will be installed 5'+ away from the neighbors wall.

